

# BOOM

## Sturgis Tile

### STURGIS TILE COMPANY LLC

**Business Address:**

**360 E Deadman Rd.**

**Sturgis, SD 57785**

**Phone: 605-347-5964**

**Email: smorell@boomcon.com**

**Office/Mailing Address:**

**PO Box 437**

**Newell, SD 57760**

**Phone: 605-456-2600**

**Fax: 605-456-6060**

#### ABOUT US...

*Sturgis Tile Company, LLC was purchased by Troy Van Der Boom in April, 2006.*

*At the Sturgis location our crews are busy manufacturing prefabricated concrete tile.*

*Although originally used for well tiles, The tiles and lids are also used for "risers" on concrete septic tanks, cisterns, and well pits.*

*Our crews are at the Sturgis Tile location spring, summer, and fall. During the "off season" your phone calls will be forwarded to the Newell office (also Boom Concrete's office), and we will make arrangements to fill your product needs.*



### TILE - REDUCERS - CAPS

#### 20" TILE



- 20" TILE: 20" INSIDE DIA, 24" OUTSIDE DIA

20" CAP (Solid)/(6" Hole)	\$ 50.00
20" FLOOR	\$ 50.00
20" SETTER	\$ 88.00
20" HALF TILE (1 ft tall)	\$ 48.00
20" FULL TILE (2 ft tall, 230 lbs)	\$ 50.00

#### 30" TILE



- 30" TILE: 30" INSIDE DIA, 36" OUTSIDE DIA

30" CAP (Solid)/(6" Hole)	\$ 60.00
30" FLOOR	\$ 73.00
30" SETTER	\$ 108.00
30" REDUCER	\$ 85.00
30" HALF TILE (1 ft tall)	\$ 58.00
30" FULL TILE (2 ft tall, 600 lbs)	\$ 80.00
30" Concrete Tile to 20" Polylok (6") includes lid	\$ 115.00

#### 42" TILE



- 42" TILE: 42" INSIDE DIA, 48" OUTSIDE DIA

42" CAP (Solid)	\$ 99.00
42" FLOOR	\$ 100.00
42" SETTER	\$ 122.00
42" REDUCER	\$ 90.00
42" FULL TILE (2 ft tall, 850 lbs)	\$ 105.00
42" Concrete Tile to 24" Polylok (12") includes lid	\$ 137.00

#### 26" CISTERN



- 26" TILE: 26.5" INSIDE DIA, 30" OUTSIDE DIA

26" CAP	\$ 55.00
26" HALF RISER (1 ft tall)	\$ 55.00
26" FULL RISER (2 ft tall)	\$ 61.00
26" Concrete Tile to 24" Polylok (12") includes lid-(Cistern Reducer)	\$ 95.00

**Sealant Tar per roll: \$15.00**